BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 **Indent No.20444**

SCHEDULE-B

NAME OF WORK: Improvements and providing name boards and stickers in Dasarahalli Ward no.15

Description of work	Unit	Qty	Rates Quoted by Contractor **RAJENDRA**		
			In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
2	3	4	5	6	7
Earthwork excavation for foundation of buildings, water supply, sanitary, lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specfication & as per direction of Engineer-in-charge	Cum	11.25	280.0	Rupees Two Hundred Eighty Only	3150.00
Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, complete as per specfication & as per direction of Engineer-in-charge	Cum	9.11	4919.0	Rupees Four Thousand Nine Hundred Nineteen Only	44812.09
Providing fabricating and fixing MS Name Board of Size 0.90X0.60 Mtrs with Vertical postd of 3.70M Hight made out of two jointly welded 65X66 mm angels with necessary hold fast weld top Name board of 18guage sheet of size 0.90X0.60Mtrs welded to angels of 25X25X4mm on all sides with all fabrication charges, Transportation and other incidental charges. complete as per specfication & as per direction of Engineer-in-charge	Nos	75	2910.0	Rupees Two Thousand Nine Hundred Ten Only	218250.00
Providing and applying painting two coats (excluding priming coat) on new Steel surface and / or Steel based surface with enamel paint to give an even shade, cleaning surface of all dirt, dust, and foreign matter, and papering including cost of materials, labour, complete as per specfication & as per direction of Engineer-in-charge	sqm	2286.2	85.0	Rupees Eighty Five Only	194330.40
Painting letters with black japan paint complete as per specfication & as per direction of Engineer-in-charge	Sqm	66000	0.32	Thirty Two Paise Only	21120.00
				Total	481662.49
				Percentage	2.89%

Rajendra

Executive Engineer

Signature of the Contractor